


SECTION A-A

STANDARD NOTES:

1. TO BE USED AS DIRECTED BY THE WPCA OR ITS TECHNICAL CONSULTANT.
2. WIRE SUPPORTS TO BE PLACED AROUND THE PIPE AND ANCHORED TO THE PRECAST CONCRETE BLOCKS TO PREVENT FLOATATION OF THE PIPE WHILE THE CONCRETE CURES.
3. WIRE SUPPORTS TO BE PLACED AROUND THE PIPE AND ANCHORED TO THE PRECAST CONCRETE BLOCKS TO PREVENT FLOATATION OF THE PIPE WHILE THE CONCRETE CURES.



Water Pollution Control Authority
Town of Canton

4 Market Street
P.O. Box 168
Collinsville, Connecticut 06022

SEWER CONSTRUCTION DETAIL

CONCRETE SEWER CRADLE

NO SCALE

LATEST REVISION: 2/07

NO. 035